

West Hartford Deck — Bill of Materials

Version: v15 plan, dated 2026-05-06 **Prepared by:** Hollis, Home-Improvement Concierge / Owner's Advocate

Scope

23'-6" × 16'-3" attached deck on existing concrete patio, West Hartford CT. Maximum 12" above finished grade. Attached to wood-frame house via 2×10 PT ledger on the 23'-6" (long) edge. Three perpendicular tripled-2×10 PT girders on 6 Pylex 50 screw piers. Face-hung 2×10 PT joists at 12" o.c., parallel to house. MoistureShield Vision composite decking perpendicular to house, 4-sided picture frame, composite fascia on 3 exposed sides. Two egress points: left-edge single-step stair (42" wide) and far-edge wide step (11'-9" long). All hardware ACQ-compatible (hot-dip galvanized or stainless).

1. Foundation & Piers

Item	Spec	Qty	Notes
Pylex 50 helical/ screw pier	50" galvanized shaft, ≥ 3" helix	6	Middle row (y=8'-1.5") and outer row (y=16'-0"); 2 per girder × 3 girders
Pylex saddle bracket	Matching Pylex 50 saddle plate	6	Bolts to shaft top; girder bears in saddle
½" HDG carriage bolt + nut + washer (saddle-to- shaft)	½" × 3½" HDG	12	2 per saddle (per Pylex install spec)
½" HDG lag bolt (girder-to-saddle)	½" × 3" HDG	12	2 per saddle, up into girder bottom
Hydraulic cement or non-shrink grout	10-lb bag	2	Patch/grout concrete around pier shaft at patio surface after install; 6 holes total
Concrete patio repair mix	Quikrete Vinyl Concrete Patcher or equiv, 10-lb tub	1	Cosmetic surface flush-fill around shaft collars

Item	Spec	Qty	Notes
Cedar or HDPE shims	Composite or rot-resistant	1 pack	Level saddles if patio surface is uneven under bearing point

Pier hole layout: 6 locations — (x=0', y=8'-1.5"), (x=0', y=16'-0"), (x=11'-6", y=8'-1.5"), (x=11'-6", y=16'-0"), (x=23', y=8'-1.5"), (x=23', y=16'-0"). Sledgehammer-punch 3–4" diameter holes through existing patio slab at each location before screwing pier.

2. Lumber — Pressure-Treated SYP, Ground-Contact (UC4B)

All PT lumber: Southern Yellow Pine, ground-contact rated (UC4B), KDAT (kiln-dried after treatment) preferred. Verify net dressed length at the yard before delivery.

2a. Ledger

Item	Size	Length	Qty	Notes
Ledger board	2×10 PT UC4B	23'-0"	1	Order as a single 24-ft board field-cut to 23'-0"; or use two 12-ft boards lapped at mid-girder point. Single board preferred for continuity.

2b. Girders (Tripled 2×10 PT)

Item	Size	Length	Qty	Notes
Girder plies	2×10 PT UC4B	16'-0" (use full 16-ft board, no cutting to length)	9	3 girders × 3 plies each; all exactly 16'-0". No special-order, no yard-net-length verification needed. Order standard 16-ft 2×10 PT and install at full board length. Add 1 extra board for

Item	Size	Length	Qty	Notes
				waste/defect: order 10 boards.

2c. Joists (Face-Hung, Two Segments Per Row)

Item	Size	Length	Qty	Notes
Joist segments (regular rows)	2×10 PT UC4B	~10'-11¼" clear span each (order 12-ft)	32	16 regular rows × 2 segments each. Each segment spans between adjacent girder faces (~10'-11¼" clear); order 12-ft, field-cut.
Doubled far-side rim — inner ply	2×10 PT UC4B	~10'-11¼" each (order 12-ft)	2	1 row × 2 segments, inner ply of doubled rim
Doubled far-side rim — outer ply	2×10 PT UC4B	~10'-11¼" each (order 12-ft)	2	Outer ply; face-hung same 2-segment pattern

Clear span between girder faces: 3 girders, each 4½" wide (3-ply 2×10 actual), two equal bays of ~10'-11¼" each. **Order 40 boards at 12-ft** (36 segments needed + ~10% waste).

2d. Blocking

Item	Size	Length	Qty	Notes
Field blocking (lateral stiffness)	2×10 PT UC4B	~10"-10¼" (joist bay width)	~46	Two blocking rows at x=5'-9" and x=17'-3"; each row spans 23'-0" with one block per joist bay at 12" o.c. ≈ 23 blocks per row. Cut from 12-ft drops.
House-side PF backing blocks	2×10 PT UC4B	~9" each	~23	Short pieces at 12" o.c. between ledger face and first joist row; back the house-side

Item	Size	Length	Qty	Notes
Drop-board sub-fascia (left side)	2×10 PT UC4B	16'-0"	1	picture-frame board Outboard of left girder outer face; backs PF cantilever. Use full 16-ft board as-is.
Drop-board sub-fascia (right side)	2×10 PT UC4B	16'-0"	1	Outboard of right girder outer face. Use full 16-ft board as-is.
Drop-board sub-fascia (far side)	2×10 PT UC4B	23'-0"	1	Outboard of far-side doubled rim outer face.

Tip: Field blocking and house-side PF blocks cut from joist drop-offs and 12-ft shorts. Order 4 extra 12-ft 2×10s beyond the joist count above to source blocking cuts.

2e. Far-Edge Step Ribbon

Item	Size	Length	Qty	Notes
Step ribbon — inner ply	2×6 PT UC4B	11'-9"	1	Doubled ribbon, inner ply; lag-bolted to outer rim/drop-board face at y=16'-0".
Step ribbon — outer ply	2×6 PT UC4B	11'-9"	1	Outer ply; through-bolted to inner ply.

Order two 12-ft 2×6 PT boards; field-cut to 11'-9" (141").

2f. Left-Edge Stair Stringers

Item	Size	Length	Qty	Notes
Cut stringers	2×10 PT UC4B	36" (from 4-ft drop) or cut from 8-ft	3	At y=6'-0", y=7'-9", y=9'-6"; each stringer is a short cut-stringer for single 6" rise.

Item	Size	Length	Qty	Notes
				Order 8-ft boards and cut 2 stringers per board.

Order 2 boards of 8-ft 2×10 PT for the 3 stringers (one board yields 2 stringers with a short drop).

2g. Lumber Order Summary

Category	Stock Size	Qty to Order
Ledger	2×10 PT 24-ft	1
Girder plies	2×10 PT 16-ft	10 (9 needed + 1 spare)
Joists + rim	2×10 PT 12-ft	40
Blocking (field + house-side)	2×10 PT 12-ft	4 (cut from drops above)
Drop-board sub-fascia (L/R sides)	2×10 PT 16-ft	2
Drop-board sub-fascia (far side)	2×10 PT 24-ft	1 (or splice 2× 12-ft)
Step ribbon (far-edge)	2×6 PT 12-ft	2
Stair stringers (left-edge)	2×10 PT 8-ft	2

3. Decking, Picture Frame & Fascia

All MoistureShield Vision composite, capped, DiamondDefense scratch coat, 50-yr fade & stain warranty. Available at Home Depot, Lowe's, Richards Building Supply (Hartford metro).

3a. Field Planks

Item	Brand / Product	Width	Thickness	Cut Length	Qty	Notes
Field decking planks	MoistureShield Vision	5.4"	1.0"	15'-7.2" (from 16-ft stock)	49	Run perpendicular to house; 1/8" gap between planks.
Field planks (ordered)	MoistureShield Vision 16-ft	—	—	16-ft boards,	54	49 needed + 10% waste =

Item	Brand / Product	Width	Thickness	Cut Length	Qty	Notes
				field-cut		53.9 → 54 boards

3b. Picture-Frame Boards (4 Sides)

Side	Length	Ordered As	Qty	Corner Treatment
House-side PF	23'-6"	24-ft board, field-cut; or 2× 12-ft spliced over a joist	1	Butt at left/right against house wall
Far-side PF	23'-6"	Same	1	45° mitered at left/right outside corners
Left-side PF	16'-3"	18-ft board field-cut to 16'-3"; or splice 2 shorter boards over a joist	1	Mitered at far corner; butt at house end. Interrupted at step opening y=6'-0" to y=9'-6"
Right-side PF	16'-3"	Same	1	Mitered at far corner; butt at house end

Left-side PF note: The step opening (y=6'-0" to y=9'-6") interrupts the left-side PF. Order as two separate cuts: house segment (6'-0") + outer segment (6'-9"). If ordering the outer segment separately, a 12-ft board is more than sufficient for 6'-9".

Side PF stock note: The side PF boards are 16'-3" — 3" over standard 16-ft boards. Order 18-ft boards or plan a splice over a joist/blocking point.

3c. Fascia Boards (3 Exposed Sides)

MoistureShield Vision composite fascia: 0.67" thick, 11.25" tall.

Side	Length	Ordered As	Qty	Notes
Far-side fascia	23'-0"	24-ft board field-cut; or 2× 12-ft	1	Full run; backs far-side PF
Left-side fascia	16'-0"	16-ft board, use full length — no cutting needed	1	Interrupted at step opening same as PF
Right-side fascia	16'-0"	16-ft board, use full length — no cutting needed	1	Full run

3d. Step Tread Planks

Location	Item	Width	Length	Qty	Notes
Far-edge step	MoistureShield Vision	5.4"	11'-9" (order 12-ft)	2	2 planks side-by-side = 10.9" tread depth, running $\perp$ house.
Left-edge stair	MoistureShield Vision	5.4"	42" (cut from 4-ft or longer)	2	2 planks side-by-side = 10.8" tread, running parallel to left edge; cut from a single 4-ft or 6-ft offcut

3e. Decking Board Order Summary

Product	Length	Qty to Order
MoistureShield Vision field planks	16-ft	54
MoistureShield Vision PF boards	24-ft (house + far sides)	2
MoistureShield Vision PF boards	18-ft (side PF — L + R)	2 (+ 2 if ordering short cuts for L-side step interruption)
MoistureShield Vision fascia	24-ft (far side)	1
MoistureShield Vision fascia	16-ft (L + R sides — exact length)	2
MoistureShield Vision step treads	12-ft (far-edge step)	1 (yields 2 tread planks)
MoistureShield Vision step treads	cut from field plank drops	2 (left-edge stair)

4. Connectors & Hangers

All connectors: hot-dip galvanized (HDG), ACQ-compatible. Simpson Strong-Tie specified throughout.

Item	Model	Qty	Notes
Girder-to-ledger hanger (tripled 2×10)	Simpson HU210-3 (or LU210-3 if HU not available in 3-ply)	3	One at each of the three girder-to-ledger intersections (x=0', x=11'-6", x=23'-0")
Joist segment face-mount hanger (regular joists)	Simpson LUS210Z HDG	68	17 rows × 2 segments × 2 hanger ends = 68
Doubled rim hanger (far-side rim, inner/outer ply)	Simpson LUS210Z HDG (single) or LUS210-2Z for doubled	4	1 row × 2 segments × 2 ends = 4
Stringer-to-girder hanger (left-edge stair)	Simpson LSCZ (skewable face-mount)	3	One per stringer (3 stringers); attaches stringer to left girder outer face
Post base / saddle (pier)	Pylex saddle bracket	6	Already counted under Foundation

Hanger count double-check: 16 regular joist rows × 2 segments × 2 ends = 64 regular + 1 doubled-rim row × 2 segments × 2 ends = 4 rim hangers. Subtotal = 68 LUS210Z in field. Plus 3 HU210-3 at ledger. Plus 3 LSCZ at left-edge stair. Add 5% overage: **order 75 LUS210Z + 3 HU210-3 + 3 LSCZ.**

5. Fasteners

All fasteners: HDG or stainless (ACQ-compatible). No electroplated zinc.

5a. Ledger-to-House

Item	Spec	Qty	Notes
Ledger lag bolts (field, between girder connections)	½" × 4" HDG lag	34	½" HDG lag at 18" o.c. two-row staggered between the three girder-connection clusters
Through-bolts at girder-to-ledger	½" × 6" HDG carriage bolt + nut + 2 washers	18	Clustered at 3 HU210-3 hanger locations; 6 per cluster; back-blocked from basement
Ledger through-bolt backup blocks	2×10 PT scrap	3 short pieces	Back-blocking behind ledger at each carriage-bolt cluster

Item	Spec	Qty	Notes
(interior band joist)			

5b. Girder Assembly (3-Ply)

Item	Spec	Qty	Notes
Ply-to-ply structural screws	GRK RSS or Simpson SDS ¼"×3" HDG	~108	3 plies × 9 boards × ~12 screws per 16-ft board = ~108
Alternate: ½" carriage bolt + nut + washer (AWC spec for 3-ply girder)	½" × 3½" HDG	~54	~2 per lineal foot × 16'-0" × 3 locations = ~48; round up to 54

5c. Joist Hangers

Item	Spec	Qty	Notes
Joist hanger nails — LUS210Z	Simpson N10 (10d × 1½") or SDS ¼"×1½" screws per Simpson spec sheet	~1,020	75 hangers × ~14 nail holes per LUS210Z = 1,050; buy 1,100
HU210-3 fasteners	Per Simpson spec (SDS ¼"×1½" or N10 as spec sheet requires for 3-ply)	~90	3 hangers × ~30 fastener holes each

Critical: Verify exact nail/screw specification on the Simpson packaging for each hanger model. Do NOT substitute nail sizes.

5d. Decking Fasteners

Item	Brand / Spec	Qty	Notes
Hidden fasteners — field planks	Tiger Claw TC-G clips	~600	~12 clips per joist row; 49 planks × ~12 clips ≈ 588; buy 625
#8 stainless screws for TC-G clips	Tiger Claw specified (stainless, 1-5/8")	~625	One per clip
Cortex face-screws + color-matched	Cortex for MoistureShield (must match Vision colorway selected)	1 box	~4 screws per lineal foot of PF × ~80 lf total ≈ 320 screws; buy

Item	Brand / Spec	Qty	Notes
plugs — PF boards			4 boxes (100-ct each)
Cortex face-screws + plugs — far-edge step treads	Cortex for MoistureShield, same colorway	included in Cortex box count above	2 planks × 11'-9"
Cortex face-screws + plugs — left-edge step treads	Same	included above	2 planks × 42"
Stainless trim screws — fascia to rim/drop-board	#10 × 2½" stainless	1 box (100 ct)	~3 screws per lineal foot × ~55 lf of fascia ≈ 165; one 100-ct box

5e. Far-Edge Step Ribbon

Item	Spec	Qty	Notes
Ribbon-to-rim lag bolts	½" × 3" HDG lag	14	~1 per 12" o.c. along 11'-9" ribbon run × 2 rows; minimum per IRC for ledger-type connection. Order 24 if through-bolting.
Ply-to-ply (ribbon inner-to-outer)	3" structural screws HDG	20	~2 per lineal foot for doubled 2×6

5f. Left-Edge Stair

Item	Spec	Qty	Notes
Stringer-to-LSCZ hanger nails	Per Simpson LSCZ spec	~30	3 hangers × ~10 nail holes
Stringer-to-paver metal anchor	Simpson MSCZ or equiv. stringer-to-pad anchor	3	One per stringer base; bears on 12×12 paver

5g. Lateral Tie Fasteners

Item	Spec	Qty	Notes
DTT2Z structural screws	SDS ¼"×4½" per Simpson spec	~32	~8 per DTT2Z device × 4 devices

6. Flashing & Moisture Protection

Item	Brand / Spec	Coverage / Size	Qty	Notes
Peel-and-stick flashing tape (ledger)	Henry Blueskin VP160 or Carlisle CCW-705	6" wide roll	2 rolls (75 lf each)	Apply to house sheathing behind ledger before ledger install; 23'-0" run
Z-flashing, aluminum	2" leg × 2" leg, 10-ft sticks	3 sticks	Tucked behind siding/ housewrap above top of ledger	
Kick-out flashing	Aluminum or plastic, pre-bent	2	At each end of ledger where siding terminates	
Joist / girder top tape	Vycor Deck Protector 2" or Trex Protect 2½"	2" wide roll, 50 lf	8 rolls	Apply to top of every joist segment, both girder tops, and ledger top before decking. Coverage ~700 lf joist tops + ~50 lf girder tops + 23 lf ledger ≈ 773 lf total; buy 16 rolls. Joist tape is required, not optional.
End-grain sealant	Copper Green Wood Preservative or Anchorseal 2	1-qt brush-on	2 qt	Seal ALL field cuts of PT lumber immediately after cutting

Item	Brand / Spec	Coverage / Size	Qty	Notes
Backer rod + polyurethane sealant	Sikaflex 1A or similar, gray	1 tube	3 tubes	Ledger-to-house seam caulk; also at far-edge step ribbon lag penetrations
Ledger spacers / standoffs	Starborn Camo LedgerUp composite or PT shims	—	as needed	If siding extends behind ledger location
Drip cap (head flashing)	Aluminum drip cap, 2" face	24-lf sticks	1 stick	Over ledger at top if housewrap alone is insufficient

7. Lateral Tie System (IRC R507.9)

Item	Model	Qty	Notes
Deck-to-house lateral connector	Simpson DTT2Z (or MTWDeck equivalent)	4	IRC R507.9 minimum; deck is 16'-3" wide. Each device connects band joist through ledger to interior floor framing. Basement accessible.

Placement: space DTT2Z devices evenly along ledger, avoiding the girder-to-ledger hanger cluster zones. Confirm exact placement with structural engineer or building official.

8. Far-Edge Step

Item	Spec	Qty	Notes
Precast concrete deck blocks	Standard 12"×12"×8" deck block (notched top for 2×)	5	Block positions at x = 23'-0", 20'-2", 17'-4", 14'-6", 11'-9" along outer edge; outside patio footprint (y > 16'-6")
#57 crushed stone (gravel pad)	¾" clean angular stone	~0.35 cu yd (≈ 10 cu ft)	4" deep × ~12'-0" long × ~18" wide

Item	Spec	Qty	Notes
			pad; level and compact before setting blocks
Landscape fabric	Woven geotextile, 4-ft wide	1 roll (12 lf used)	Under gravel pad to suppress weeds and hold stone
2×6 PT ribbon boards	UC4B, 12-ft stock	2 (already in lumber section)	Inner + outer ply, each 11'-9". Ribbon attaches to rim at y=16'-0".
Lag bolts ribbon-to-rim	½" × 3" HDG	14–24 (already in fasteners)	Per IRC connection spec
MoistureShield Vision tread planks	5.4" × 12-ft	2 (yields 2 × 11'-9" treads)	2 planks side-by-side = 10.9" tread depth

Seasonal heave callout (Hollis): Precast blocks on gravel will heave ¼–½" seasonally — no frost-depth anchoring. Homeowner has accepted this. Do not use hydraulic cement to lock blocks. Check level each spring.

Exposed patio strip: The existing patio is 23'-6" × 16'-6"; the deck covers 23'-6" × 16'-3" to the PF outer edge. A 3" × 23'-6" strip of bare concrete patio remains visible along the outer far edge. The right half (~11'-9") is partially screened by the far-edge step assembly; the left half (~11'-9") is open. Patio drains fine and there is no structural concern — purely cosmetic. Options: leave as a neat narrow reveal; add a decorative gravel border; or place a row of narrow concrete pavers. Decide after the deck is built and you see it in context.

9. Left-Edge Stair

Item	Spec	Qty	Notes
12"×12" concrete paver	Standard Holland or Barkman, min. 2" thick	4	Landing pad under stringer ends; 4 pavers in 2×2 layout
#57 crushed stone (paver base)	¾" clean angular	~0.15 cu yd (≈ 4 cu ft)	4" deep × 48" wide × 18" deep pad under pavers
Landscape fabric	Woven geotextile	from same roll as far-edge step	Under gravel bed
PT 2×10 cut stringers	UC4B, 8-ft stock	2 boards → yields 3 stringers	Single 6" rise; Simpson LSCZ hangers to left girder; stringer base rests on pavers

Item	Spec	Qty	Notes
MoistureShield Vision tread planks	5.4" × cut from field-plank drops	2	2 planks × 42" = middle tread at 6" AG
Metal stringer anchor (paver-to-stringer)	Simpson MSCZ or rigid strap anchor	3	Secure stringer bottom to paver

10. Easy-to-Forget Small Stuff

Item	Spec	Qty	Notes
Mason's string lines + line level	300-ft reel + 2 line levels	1 set	Layout ledger elevation, girder tops, and pier positions
Chalk line + chalk (blue)	100-ft chalk line	1	Mark joist positions on girder tops, blocking rows, pier hole centers
Marking paint (inverted spray)	White or orange	2 cans	Mark pier locations on patio surface before punch
Angle grinder + diamond cup wheel	Rental	1 day rental	Clean up pier hole edges in concrete slab
Cold chisel + 3-lb hammer	—	1 set	Finish squaring up punched pier holes
Plastic sheeting 6-mil	10'×25' roll	1	Protect staged framing lumber from rain
Heavy-duty tarp (canvas or poly)	12'×20' minimum	1	Cover MoistureShield decking bundles during construction
Deck cleaner / brightener	Defy Composite Deck Cleaner or similar	1 gal	Pre-clean before final inspection
Board spacer gauges (1/8")	Tiger Claw spacer or paint-stir sticks	1 bag	Consistent gap during decking install
Screw gun bits for TC-G clips	#2 Robertson (square) or per Tiger Claw spec	5 bits	TC-G clips strip bits quickly on a long run
Cortex plug installation tool	Cortex driver bit (included in Cortex box)	confirm in box	Setting plugs flush
Safety glasses, hearing protection	—	1 each per worker	Required for hammer-drilling, cutting
Knee pads	—	1 pair	Decking installation

Item	Spec	Qty	Notes
Sawhorses	—	2 pair	Cutting station
Circular saw with carbide blade	40-tooth for composite decking; 24-tooth for PT	1 each	Use separate blades — composite dulls blades fast
Jigsaw	—	1	Notch cuts; step opening cut joints in PF
Drill-driver + impact driver	—	1 each	Drill for pilot holes, impact for driving
½” spade bit or auger bit	—	1	Pilot holes for lag bolts
Torque wrench (½” drive)	—	1	Snug-tight carriage bolts at ledger clusters and pier saddles
Speed square + framing square	—	1 each	Joist layout checks
25-ft tape measure	—	2	Lose one daily; keep a spare
Level (4-ft and 2-ft)	—	1 each	Saddle leveling, ribbon height
Reciprocating saw + bi-metal blades	—	1	Cut off protruding stringer ends; notch PT
Pencil (carpenter’s) + Sharpie	—	6 pencils, 2 markers	Mark cuts; Sharpie on tape for dim references
Lag bolt socket set (½” and 9/16”)	—	1	Driving lags with impact wrench
Impact wrench (½” drive)	—	1	Seating carriage bolts at ledger clusters

11. Optional / Phase 2

Item	Notes
Deck lighting conduit rough-in	If any low-voltage lighting planned, run 1” PVC conduit under decking before field planks go down. Impossible to retrofit without removing planks.
Railing (if required)	IRC R312 requires guardrail at decks $\geq$ 30” AG. This deck is $\leq$ 12” AG throughout — no railing required by code. Decorative rail along far edge is an option if children are frequent users.

Item	Notes
Skirt lattice / under-deck trim	3 exposed sides have MoistureShield fascia and PF overhang; the ~1.75" AG gap under framing is visible. Composite lattice panels or a solid skirt board can close this if aesthetics require it. Confirm any skirt allows drainage.
Downspout extensions	If gutters discharge near any pier location or the step gravel pads, extend downspouts ≥ 4 ft away from deck perimeter. Check on-site before framing.
Exposed patio strip edging	A 3" $\times$ 23'-6" strip of bare concrete is visible at the far edge of the patio (between PF outer edge and patio edge). Options: (a) leave as-is — purposeful narrow reveal; (b) a line of narrow concrete pavers or decorative gravel; (c) a thin composite trim rip if aesthetic preference. Low priority; cosmetic only.

Notes for the Homeowner

A. Order PT lumber early. Kiln-dried-after-treatment (KDAT) is the right spec — drier, straighter, less post-install shrinkage. May need 1–2 weeks lead time. Call Richards Building Supply or Curtis Lumber (West Hartford area) early.

B. Girder plies are standard 16-ft boards — no yard-net-length question. The 9 girder plies are exactly 16'-0" — order standard 16-ft 2 $\times$ 10 PT and use at full board length. No special ordering, no trimming.

C. Side fascia fits 16-ft boards exactly. Left-side and right-side MoistureShield Vision fascia boards are exactly 16'-0" — order 16-ft fascia boards and use full length.

D. Side PF boards still need 18-ft stock. The left-side and right-side PF boards are 16'-3" (they extend from house wall to PF outer edge = 16'-0" rim + 3" cantilever). That's 3" over a standard 16-ft board. Order 18-ft MoistureShield Vision boards for these two pieces, or plan a splice over a joist/blocking point.

E. Mark outer pier hole positions carefully before punching. Outer pier row is at y=16'-0". Confirm marks before drilling or punching concrete.

F. Cortex plug color must match your MoistureShield Vision colorway. Select your Vision color first, then order Cortex in the matching color. Do not substitute generic composite plugs.

G. Verify joist-hanger nail spec on Simpson packaging. LUS210Z calls for N10 (10d $\times$ 1½") or SDS ¼" $\times$ 1½" structural screws. The HU210-3 has its own spec. Read both spec sheets at time of purchase.

H. Check West Hartford building permit before lumber delivery. Decks ≥ 200 sq ft attached to house require a permit in West Hartford. Have Pylex load data sheet, lateral tie device (DTT2Z), and joist/girder species/grade ready for plans examiner.

I. Exposed patio strip — cosmetic note. The existing patio is 23'-6" $\times$ 16'-6". The deck covers 23'-6" $\times$ 16'-3" of the patio to the PF outer edge. A 3" $\times$ 23'-6" strip of bare concrete patio is visible along the outer far edge. The right half (~11'-9") is partially obscured under the far-edge step assembly; the left half (~11'-9") is open and visible from beyond the deck. This is entirely cosmetic — the patio drains fine. Options: leave it as a neat narrow reveal (simplest); add a decorative gravel border; or place a narrow strip of concrete pavers. The 3" width is about the width of a large brick course — not sloppy, just a narrow transition. Decide after the deck is built and you see it in context.

J. Seasonal heave on far-edge step. The 5 precast blocks for the far-edge step are NOT frost-protected. Expect $\frac{1}{4}$ – $\frac{1}{2}$ " of seasonal lift and resettlement each year. Normal and accepted. Do not grout blocks in place. Check level each spring.

K. End-grain sealing is not optional. Every cut end of every PT board must be sealed with Copper Green or Anchorseal 2 immediately after cutting. Keep the sealant can at your saw station.

L. Joist tape goes on before decking. Apply Vycor Deck Protector to the top face of every joist, girder, and ledger before installing any decking plank. Joist tape is required, not optional.

Bill of Materials for the West Hartford deck (v15 plan, dated 2026-05-06). Prepared by Hollis — Home-Improvement Concierge / Owner's Advocate. Print this document and bring it to the lumber yard and hardware store. Quantities include waste factors where noted; consult your contractor or permit plans for final structural verification.